

Job Name/Location:

Tag #:

Date:	For: File Resubmit
PO No.:	Approval Other_____
Architect:	GC:
Engr:	Mech:
Rep:	
(Company)	(Project Manager)

## PREMTC00U Simple Remote Controller



### Unit Data:

Maximum No. of Indoor Units (Group Control)	16
Temperature Value*	Fahrenheit (1° Increments) / Celsius
Dimensions	4-3/4" L x 2-3/4" W x 5/8" H
Weight	0.18 lbs.

\*Temperature Value depends on equipment.

### Operating Range:

Cooling (°F DB)	64 ~ 86
Heating (°F WB)	60 ~ 86

### Communications Cabling Specifications (V-Net):

Type	Included with Remote Controller
Length**	33 feet
Type	Field Supplied
Length**	164 feet
Size	22-3 AWG, twisted, stranded, unshielded

\*\*Communication cable can be extended to a maximum of 164 feet by using the Wired Zone Controller Extension Cable - PZCWRC1 (maximum four [4] kits), or field wire.

### Standard Features:

- Auto Operation (Dual Setpoint)
- Unit Operation – On / Off
- Mode Selection – Cool / Heat / Dry / Fan / Auto
- Fan Speed Selection
- Air Flow Direction (available with indoor units equipped for this feature)
- Static Pressure Setting
- Child Lock
- LED Indicator for unit operating status
- Master / Slave Setting for Multiple Controller Installation
- Room Temperature Sensing Location (Zone Controller, Indoor Unit, Two-Thermistor)
- Discharge Vanes – Auto Swing / Fixed (available with indoor units equipped for this feature)
- Manual Central Control Addressing

### Optional Accessories:

- ☐ 33-foot Extension Cable Assembly (PZCWRC1)
- ☐ Group Control Cable Kit (PZCWRCG3)

### Notes:

1. Must follow installation instructions in the applicable LG installation manual.
2. Available functions / features may differ based on the connected system.

