





Stainless Frame

Key Features

- Convection cooling system provides a quick cool down and consistent temperature
- Extended lower interior maximizes storage options
- Black interior
- LowE coated, argon gas filled, dual thermopane glass door provides protection from harmful UV Light
- Stainless steel grille and full-wrap door
- Four fixed black wine racks
- Wine racks accommodate a variety of bottle sizes including champagne and magnum bottles

- Digital touch pad control
- Temperature range: 34°F to 60°F
- Bright white LED lighting
- Volume of 5.7 cu ft holds up to 38 wine bottles (750 ml)
- Stainless steel handle (1/8" diameter)
- Field reversible door is shipped right-hand hinged
- Built-in or freestanding
- Four adjustable leveling legs


Model Details

| Model | Voltage/Hz | Door Swing | Finish | Shipping Weight |
|---------------|------------|------------------|-----------------|-----------------|
| UHWC024-SG01A | 115 / 60 | Field Reversible | Stainless Frame | 124 lb |

Accessories

| Model | Description | Finish | Shipping Weight |
|---------------|------------------|--------|-----------------|
| ULAFREESTANDB | Freestanding Kit | Black | 3 lb |







Specifications

| Model | HWC024 | |
|-----------------------------------|---|--|
| Amps: Running (115 v) | 1.2 A | |
| Capacity: Wine Bottle (750 ml) | 38 | |
| Capacity: Volume (cu ft) | 5.7 | |
| Dimensions: Product Depth | 22 ½" / 572 mm | |
| Dimensions: Product Height | 34 ½" / 867 mm | |
| Dimensions: Product Width | 23 ¹⁵ / ₁₆ " / 608 mm | |
| ENERGY STAR | No | |
| Energy Consumption: Avg. Per Year | 278 kWh | |
| Refrigerant Type | R600a | |
| Sabbath (Star K Certified) | Yes | |
| Temperature Range | 34°F to 60°F | |

Back



Cabinet Cut-Out



Warranty

- 1 Year (parts & labor) / 5 year sealed system (parts)
- + Additional 1 Year (parts & labor) warranty at no cost with product registration

See complete warranty for details



Installation Notes

- 24" cutout width sufficient if door protrudes beyond adjacent cabinetry
- No additional clearance is needed for ventilation
- Do not obstruct front grille air flow







